

**DEPARTMENT OF DISTANCE AND CONTINUING EDUCATION
SCHOOL OF OPEN LEARNING
(CAMPUS OF OPEN LEARNING)
UNIVERSITY OF DELHI
DELHI-110007**

Notice Invite Quotation

Endt. SOL/Gen.(M)/2026-27/179

Date: 29/09/2026

Sealed percentage rate quotations are hereby invited from the working contractors registered with CPWD/MES/Railways/Delhi PWD/University of Delhi, etc., for **"Replacement of damaged Tin-Shed Roofing over Room No. 33 at West Regional Centre, Keshavpuram SOL, University of Delhi"** so as to reach the Office of the undersigned up to 01:00 pm on 01/10/2026

S.No	Item	Unit	Qty	Rate	Amount
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	sqm	116.84	164.95	19272.70
2	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	116.84	738.65	86303.80
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	175.1	133.70	23410.80
4	Providing and fixing pre-coated galvanised steel sheet roofing accessories of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05 mm) with Zinc coating 120 gram per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500 - 600mm)	metre	37	532.35	19696.90
				Total	148684.20

Condition:

1. The work should be completed within 07 (Seven) days from the issue of work order.
2. CPWD specification and other mandatory norms should be followed.
3. The bill should be raised in favour of Principal, School of Open Learning. D.U.
4. 1.50 % water/electricity charges will be deducted from bill.

Ay
Principal

1. I/we hereby quote _____% above/below/at par on the estimated cost of Rs. 1,48,684.20/-
(Rupees One Lakh Forty-Eight Thousand Six Hundred Eighty-Four and Paise Twenty Only)
2. Undertaking I/we hereby undertake that my/our agency have not been blacklisted/debarred in any Govt. Organization since last 3 years.

(Contractor)